



1 KITCHEN FLOOR PLAN
SCALE: 1/2"=1'-0"



GENERAL NOTES	
1.	(E) FOUNDATION CONDITIONS TO BE VERIFIED BY CONTRACTOR IN THE FIELD.
2.	(E) FIRST FLOOR CONDITIONS TO BE VERIFIED BY CONTRACTOR IN THE FIELD.
3.	REMOVE (E) MECHANICAL SYSTEM COMPONENTS ONLY TO THE EXTENT REQUIRED TO COMPLETE DEMOLITION. PROTECT AND RETAIN EXISTING MECHANICAL COMPONENTS FOR REUSE WITH (N) CONSTRUCTION.
4.	SALVAGE ALL DOOR & CABINET KNOBS, HINGES, AND HARDWARE.
DEMOLITION PLAN LEGEND	
	(E) TO BE REMOVED AND DISPOSED OF UNLESS OTHERWISE INDICATED.
	(E) FINISH FLOOR MATERIALS TO BE REMOVED AND DISPOSED OF. REMOVE (E) SUBFLOOR SHEATHING AS REQUIRED TO PERFORM STRUCTURAL, MECHANICAL, AND ELECTRICAL WORK.
DEMOLITION PLAN KEYNOTES	
1	REMOVE AND DISPOSE OF (E) CONCRETE SLAB AND EXCAVATE AS REQUIRED.
2	REMOVE AND DISPOSE OF (E) FLOOR STRUCTURE AND EXCAVATE AS REQUIRED.
3	REMOVE AND DISPOSE OF (E) PERIMETER FOUNDATION.
4	REMOVE AND DISPOSE OF (E) WINDOW.
5	REMOVE AND DISPOSE OF OR MODIFY (E) EXTERIOR WALL TO ACCOMMODATE (N) STRUCTURAL WORK AND WINDOW INSTALLATION.
6	REMOVE (E) DOOR AND RE-INSTALL.